BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/04/2020-21 Dated: 11-08-2020

APPROVED TENDER SCHEDULE –'B'

Item 14

Name of Work :-Construction of RCC drain and culverts at balance roads Brundavana layout and Santhoshnagara (Law College) and surrounding areas in ward no:03 Attur of Yelahanka satellite town sub division.

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri R RANGANATH	
				Rate	Rate in Words
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	1167.80	229.77	Two Hundred TwentyNine Paise SeventySeven Only
2	Filling in foundation with granite/trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. a) 40mm Jelly	Cum	0.62	1981.79	One Thousand Nine Hundred EightyOne Paise SeventyNine Only
3	b) 20mm Jelly	Cum	0.62	1981.79	One Thousand Nine Hundred EightyOne Paise SeventyNine Only
4	c) Coarse sand.	Cum	0.47	2763.67	Two Thousand Seven Hundred SixtyThree Paise SixtySeven Only
5	d) Fine Sand	Cum	0.31	2763.67	Two Thousand Seven Hundred SixtyThree Paise SixtySeven Only
6	e) 12.5mm chips	Cum	0.47	1981.79	One Thousand Nine Hundred EightyOne Paise SeventyNine Only

	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 984- 995 with latest amendments and conveyingto work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. (Perforated Pipe for Rain Water Harvesting Pit) (BWSSB SR 2017-18, Pg No 121 Item No. 1.17 Code No. K010Q)	m	9.00	11282.27	Eleven Thousand Two Hundred EightyTwo Paise TwentySeven Only
8	Providing of Geonets for Rain Water Harvesting pit on top of the filter media as specified indrawings or as approved by Engineer Incharge. Data Rate	Sqm	1.55	74.05	SeventyFour Paise Five Only
9	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)	Cum	137.06	5652.33	Five Thousand Six Hundred FiftyTwo Paise ThirtyThree Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಿಭಾಗ
ಬಿ.ಡಬ್ಲ್ಯು.ಎಸ್.ಎಸ್.ಬಿ. ಬೆಂಗಳೂರು - 560064

	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19)	Cum	448.56	7370.68	Seven Thousand Three Hundred Seventy Paise SixtyEight Only
11	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)	Tonne	26.91	77136.91	SeventySeven Thousand One Hundred ThirtySix Paise NinetyOne Only
12	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	1121.40	2436.32	Two Thousand Four Hundred ThirtySix Paise ThirtyTwo Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.